BRUHAT BANGALORE MAHANAGARA PALIKE

Mofidied Schedul -B

Name of works: Modified Estimate for Repairs and Maintenance of Roads and Drains in Ward No 06 Byatarayanapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Issued to Technical Manager, KRIDL	
				In Figures	In Words
1	448.48	KSRRB300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications. .	Cum	170.70	Rupees One Hundred Seventy And Paise Seventy Only
2	35.18	KSRRB M2100-10. Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications.	Cum	4800.00	Rupees Four Thousand Eight Hundred Only
3	5.85	KSRRB M2200-6. Providing TMT Bars Fe 500 steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking, placing in postion, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specification	Tonne	68000.00	Rupees Sixty Eight Thousand Only
4	111.41	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. With 20mm and sown size granite metal course aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compcted for walls and bottom including centring shuttering cost of material HOM of machinary curing etc., complete execluding cost of steel as per MORTH specification no. 1500, 1700, 2200 including cost of material labour HOM complete as per specification.	Cum	6300.00	Rupees Six Thousand Three Hundred Only
5	292.50	Providing and fixing RCC precast cover slab of 100mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate)	Sqm	1900.00	Rupees One Thousand Nine Hundred Only
6	73.20	Providing and fixing RCC precast cover slab of 230mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate)	Sqm	4500.00	

Contractor

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Scanned by CamScanner